



**OFFICE OF THE MUNICIPAL COUNCILLORS OF KHARDAH**  
**KHARDAH MUNICIPAL OFFICE**  
**B.T.ROAD, KHARDAH, NORTH 24-PARGANAS, KOLKATA – 700 117**

No. *Kdl/Com/121/19*

Date *02/02/19*

**NOTICE INVITING TENDER**

Sealed quotations are invited from the bonafied, reliable and resourceful Agencies for Electric Point wiring, Repair/Replacement of certain light fittings converted into LED light fittings including internal electrification and associated works in 'SARAT SADAN' Ceremonial Hall under Khardah Municipality.

Sl. No.	Description	Quantity	Rate	Amount
1.	Material and labour for point wiring complete with 1.5 sq.mm. PVC insulated, FRLS type ISI marked conforming to IS-694/1990 unsheathed multi-stranded, single core, copper conductor cable 1100 Volt grade colour coded cable drawn through and including PVC casing and capping/conduit 20mm. medium grade and cutting, casing work at any height and all accessories concealed in wall/roof etc. fixing of top cover blanking plate as per numbers of switches, sockets, fuse/MCB, fan regulators etc. including 1.5 sq.mm. PVC insulated multi-stranded FRLS type(Green) colour single core cable with copper conductor cable as earth continuity conductor complete all as specified and directed with labour charge.	25 Nos.		
2.	Providing and fixing decorative box type 18/20 Watt LED Tube light prewired and including providing single side LED tube rod 18/20 Watt- 01 No. including PVC wooden round/square block- 02 Nos. and connected with LED fittings to ceiling rose and including removing old unserviceable fittings complete all as specified and directed make of LED light fitting. Brand: SURYA/Crompton	60 Nos.		
3.	Supply and fixing sheet metal enclosure with metal type acrylic door 415 Volt, AC VTPN DB Vertical type distribution board 6 way/8 way/12 way for flush mounting with 200 Amps copper busbar 2 neutral/earth bar for ease of installation and MCCB incomer of rating up to 200 Amps, FP and MCB/SP/TP MCBs as outgoing complete connecting cable link with top and bottom with IP54 DB's protection and including making good distribution with all charges etc. complete.	03 Jobs		
4.	Supply and fixing of handmade Tuni LED light set, the same as fixing by G.I Wire& connected by 1.5 sq.mm copper wire mainline from roof to first floor outside of the building including labour charge complete in all respect.	20 Set		
5.	Supply and fixing of decorative LED Jhar Lantern for the balcony of this building. This light will look very nice and current consumption will be less. The following enquiries are required for installation and wiring charge complete in all respect.	03 Set		
6.	Material and labour for 6pin 6/16 Amps socket outlet point controlled by one 16 Amps switch on independent board, wiring complete with 4.0 sq.mm PVC insulated FRLS type ISI marked conforming to IS/694 /1990 multi-stranded single core copper conductor cable 1100 Volts grade colour coded cables drawn through and including PVC casing and capping ISI marked as required at site all necessities suitable for mounting 1.5 sq.mm PVC insulated multi-stranded unsheathed (green colour) FRLS type single core cable as earth continuity including all labour etc. charges complete in all respect.	8 Nos.		

Quotations are to be enclosed with quotation paper, the valid Trade Licence, GST. No. I.T. & P.T. Certificates. The Municipality resumes the right to accept or reject any quotation or part thereof. The Municipality does not bind itself to accept the lowest quotation. The last date of receiving quotation paper is 12.02.2019 up to 12.00 noon and will open on the same date at 3.00 PM.

Sd/- TAPOSH PAUL  
 CHAIRMAN  
 KHARDAH MUNICIPALITY

*Taposh Paul*

TAPOSH PAUL  
 CHAIRMAN  
 KHARDAH MUNICIPALITY

Copy to-

1. The Councillor In Charge (Electric Deptt.)
2. The Finance Officer
3. The Accountant
4. The Electric Department
5. Notice Board

Phone: 2553-3060 / 2583-4943, FAX: 2563-1171

Email: [khardahmunicipality@yahoo.co.in](mailto:khardahmunicipality@yahoo.co.in)